



APPROXIMATELY 30"–36" OF MAIN MUST BE REMOVED TO INSTALL TEE

NOTE:

1. THE TEE MUST HAVE $\frac{3}{4}$ " – 0" BACKFILL KNIFED IN UNDERNEATH FOR SUPPORT. OLWS REQUIRES A MAIN LINE TV INSPECTION AFTER COMPACTION TAKES PLACE TO CONFIRM PROPER ALIGNMENT.
2. OLWS CODE DOES NOT ALLOW THE INSTALLATION OF A 6" INSERTA TEE ON AN 8" MAIN LINE AS IT WEAKENS THE STRUCTURAL INTEGRITY OF THE MAIN LINE. INSTEAD, A SECTION OF MAINLINE MUST BE REMOVED AND AN 8"x 6" PVC TEE SPLICED IN TO PROVIDE THE NEW TAP. NOTE THAT THIS OPERATION WILL REQUIRE THE SUBMISSION OF A WRITTEN "PUMP AROUND PLAN" FOR OLWS REVIEW.

NO.	REVISIONS	DATE	BY
1	REMOVED COUPLER JOINT ON TEE	1/9/2019	HSO
2	NOTE CORRECTIONS	3/5/2024	TAP
3			
4			